


## NOTES:

- PROVIDE 1 DAY PROGRAMMABLE THERMOSTAT.
- 2 ROUTE PRIMARY CONDENSATE DRAIN LINE TO OUTSIDE AND TERMINATE 12" AFG.
- 3 SCHEDULE 40 PVC VENT AND COMBUSTION AIR INLET SIZING AND INSTALLATION PER MANUFACTURER'S REQUIREMENTS.
- 4' EXHAUST DUCT TO OUTSIDE AT AN APPROVED CAP. MINIMUM 10 FT FROM NEAREST AIR INTAKE. EXHAUST FAN TO RUN CONTINUOUSLY TO SATISFY ASHRAE 62.2 WHOLE-BUILDING VENTILATION. (66 CFM = (((5+1) x 7.5) + (2,069 x 0.01)))
- 5 4' PRYER DUCT TO WALL OR ROOF CAP. LIMIT TO (2) 90° ELBOWS AND 14' OF DUCT.
- KITCHEN HOOD EXHAUST SYSTEM TO BE INSTALLED PER MANUFACTURER'S REQUIREMENTS. EXHAUST DUCT ROUTE TO OUTSIDE TO TERMINATE TO AN AUTOMATIC OR GRAVITY DAMPER. (100 CFM MINIMUM)
- OA CONNECTION AT RAG. VOLUME CONTROL DAMPER SET TO CFM SHOWN IN CALCULATION ON SHEET M-001.

## GENERAL NOTES:

- ALL HEATING AND COOLING EQUIPMENT HAS BEEN SIZED IN ACCORDANCE WITH ACCA MANUAL J REQUIREMENTS.
- ALL DUCTWORK HAS BEEN SIZED IN ACCORDANCE WITH ACCA MANUAL D REQUIREMENTS.
   PROVIDE UNDERCUT ON ALL BEDROOM DOORS.
- PROVIDE UNDERCUT ON ALL BEDROOM DOORS.
   ROUTE ALL EXTERIOR PENETRATIONS AWAY FROM FRONT OF BUILDING.





7010 Easy Wind Dr. Ste 200 Austin, TX 78752 512.899.3100

www.designopa.com



## TEXAS AVE. ON, NEVADA

FINAL NOT FOR BLDG DEPT

2018 OPA Design Studio. All Rights Reserved. These designs / drawings are the sole property of the Architect, OPA Design Studio. They may not be reproduced in any form, by any method, for any purpose without previous written permission from the Architect.

